ELECTRICAL DEMOLITION NOTES

1. CONTRACTOR SHALL REMOVE AND LEGALLY DISPOSE OF ALL ELECTRICAL ITEMS SCHEDULED FOR REMOVAL ALL UNDER THIS CONTRACT.
2. IT IS THE INTENT OF THIS CONTRACT TO PROTECT BRANCH CIRCUIT WIRING FOR FEEDERS TO EXISTING 480/277V PANELS AND FOR 120V BRANCH CIRCUIT WIRING FOR MISCELLANEOUS LOADS (CONVENIENCE RECEPTACLES, LIGHTING, MECHANICAL EQUIPMENT, ETC.) WHERE FEED FROM BRANCH CIRCUIT PANELBOARDS OUTSIDE OF THE MEZZANINE, THE CONTRACTOR IS REQUIRED TO IDENTIFY & PROTECT THESE CIRCUITS IN THE FIELD.
3. COORDINATE DISCONNECTION OF ANY POWER SOURCE WITH DIVISION. 15 & CRRA. THERE SHALL NOT BE ANY POWER DISRUPTION THROUGHOUT THE BUILDING DURING THE REMOVAL OF EXISTING MECHANICAL EQUIPMENT. EXISTING DISTRIBUTION SHALL NOT BE SHUT DOWN AT ANY TIME, UNLESS AUTHORIZED BY CRRA.
4. SCHEDULE ALL FIRE ALARM OUTAGES WITH CRRA.
5. CONTRACTOR IS REQUIRED TO IDENTIFY EXISTING POWER SOURCES TO EXISTING MECHANICAL EQUIPMENT FOR REMOVAL. REMOVE ALL ASSOCIATED ELECTRICAL RACEWAY, WIRING BACK TO ORIGINAL SOURCE. UPDATE EXISTING PANELS AND DISTRIBUTION SOURCE IDENTIFICATION LABELS.
6. CONTRACTOR TO REMOVE ALL CONDUIT, WIRING, HANGERS, ETC. BACK TO SOURCE PANELS

MECHANICAL DEMOLITION NOTES

1. REMOVE ALL EXISTING DUCTWORK, DIFFUSERS, GRILLS & INSULATION.
2. REMOVE ALL EXISTING AIR HANDLING UNITS, AHU-1 & AHU-2 AND MAKE UP AIR FAN MAF-1.
3. REMOVE EXISTING DUCTED AIR COOLED CONDENSING UNIT CU-2.
4. REMOVE EXISTING ROOF MOUNTED AIR COOLED CONDENSING UNITS. RECLAIM REFRIGERANT.
5. REMOVE ALL REFRIGERANT PIPING AND ACCESSORIES.
6. REMOVE ALL TEMPERATURE CONTROLS, WIRING AND ASSOCIATED CONDUIT.
7. CUT BACK EXISTING HEATING HOT WATER PIPING BACK TO RISER IN CONTROL ROOM. IN GALLERY, REMOVE PIPING BACK TO SOURCE AND CAP.
8. REMOVE CONDENSATE DRAIN PIPING.



2 CONTROL ROOM / VISITOR AREA - MEZZANINE MECHANICAL DEMOLITION PLAN
SCALE: 1/8" = 1'-0"



1 CONTROL ROOM / VISITOR AREA - UPPER ATTIC MECHANICAL DEMOLITION PLAN
SCALE: 1/8" = 1'-0"

PROJECT NORTH

CONNECTICUT RESOURCES RECOVERY AUTHORITY
TEL. NO. (860)-757-7700
FAX. NO. (860)-757-7743

A&E FIRM
URS
URS CORPORATION AES
500 ENTERPRISE DRIVE
ROCKY HILL, CT. 06067
1-(860)-529-8882

A&E SEAL

THE INFORMATION CONTAINED IN THIS SET OF DOCUMENTS IS PROPRIETARY BY NATURE. ANY USE, DISCLOSURE OTHER THAN THAT WHICH RELATES TO CRRA AND MDC IS STRICTLY PROHIBITED.

REVISIONS

NUMBER	DATE	REMARKS

CONTROL ROOM HVAC SYSTEMS IMPROVEMENT

300 MAXIM ROAD
HARTFORD, CT.

PROJECT NO:	36937520.00001
DRAWN BY:	DEP
CHECKED BY:	VMD
DATE:	04/28/08
CADD FILE:	AS NOTED

CONTROL ROOM/ VISITOR AREA MECHANICAL/ELECTRICAL DEMOLITION PLAN

MED-101

P:\Disciplines\Mechanical\Sheet\MED-101.dwg April 30, 2008 - 11:19 AM